

GENERAL NOTES:

1. ALL FASTENERS SHALL BE IN ACCORDANCE WITH THESE DRAWINGS. SPECIFIED ANCHOR EMBED TO BASE MATERIAL SHALL BE BEYOND WALL FINISH OR STUCCO.
2. OPENINGS, BUCKING & BUCKING FASTENERS MUST BE PROPERLY DESIGNED & INSTALLED TO TRANSFER WIND LOADS TO THE STRUCTURE.
3. THESE NON-IMPACT RATED WINDOW SYSTEM INSTALLATIONS ARE IN ACCORDANCE WITH AND MEET THE REQUIREMENTS OF THE FLORIDA BUILDING CODE (FBC).
4. ALL ANCHORS SECURING WINDOW FRAME TO PRESSURE TREATED BUCKS OR WOOD FRAMING SHALL BE CAPABLE OF RESISTING CORROSION CAUSED BY THE PRESSURE TREATING CHEMICALS IN THE WOOD.
5. MATERIALS, INCLUDING BUT NOT LIMITED TO STEEL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF FLORIDA BUILDING CODE CHAPTER 20.
6. TO THE BEST OF OUR KNOWLEDGE, THE WINDOWS SHOWN HEREIN ARE CERTIFIED & QUALITY ASSURED BY A FLORIDA STATE APPROVED CERTIFICATION/QA ENTITY & SHALL BE LABELED IN ACCORDANCE WITH THE FBC AND THE 9N-3 FLORIDA BUILDING COMMISSION SPECIFICATIONS. WINDOW ASSEMBLY IS NOT PART OF THIS DRAWING AND SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S QUALITY ASSURANCE SPECIFICATIONS & TESTING REPORTS.
7. CERTIFICATION OF THESE WINDOW INSTALLATIONS SHALL BE CONSIDERED VOID IF ANY OF THE FOLLOWING APPLY: 1) THEY ARE INSTALLED WITHOUT A BUILDING PERMIT FROM THE APPLICABLE LOCAL BUILDING DEPARTMENT. 2) IF THEY ARE INSTALLED BY ANYONE OTHER THAN A LICENSED CONTRACTOR EXPERIENCED WITH WINDOW INSTALLATIONS. 3) IF CHANGES HAVE OCCURRED TO THE PRODUCT'S CERTIFICATION ENTITY'S CERTIFICATE THAT CAUSE THESE INSTALLATIONS TO BE INCORRECT OR INCONSISTENT WITH WHAT HAS BEEN TESTED.
8. THE LEAST DESIGN PRESSURE SPECIFIED EITHER IN THIS DRAWING OR IN THE PRODUCTS CERTIFICATION SHALL CONTROL FOR THE INSTALLED WINDOW.
9. THESE DRAWINGS CERTIFY THE WINDOW INSTALLATION ONLY. WATER PROOFING OF THE INSTALLED WINDOWS IS NOT PART OF THIS INSTALLATION CERTIFICATION. THAT RESPONSIBILITY SHALL BE THAT OF THE MANUFACTURER &/OR INSTALLER.

ALTERNATE ANCHOR/SUBSTRATE EVALUATION NOTE:

ALL ALTERNATE ANCHORS IN THEIR SPECIFIED SUBSTRATES HAVE BEEN ANALYZED IN ACCORDANCE WITH THEIR APPLICABLE STANDARD(S) AND ARE FOUND TO BE EQUIVALENT TO OR STRONGER THAN THE ANCHOR(S) USED IN TESTING WITH THIS PRODUCT.

INSTALLATION EVALUATION IS BASED ON APPLICABLE ANCHOR STANDARDS AND/OR INFORMATION & RESULTS FROM APPLICABLE TEST REPORTS. THE FLORIDA BUILDING CODE VERSION CONSIDERED WITH THE EVALUATION WAS THAT IN FORCE AT THE TIME OF THE EVALUATION. IN THE EVENT OF CODE VERSION CHANGES/UPDATES OR IN THE EVENT THAT NEW OR ADDITIONAL TESTING IS COMPLETED ON THE REFERENCED PRODUCT, PRIOR TO STATING CODE COMPLIANCE WITH THE STATE, THE MANUFACTURER SHALL CONFIRM WITH THE INSTALLATION EVALUATION ENGINEER OF RECORD THAT THE INSTALLATIONS SPECIFIED HERE-IN ARE CURRENT WITH THE THEN CURRENT TESTING, CODE AND APPLICABLE STANDARDS.


FRAME ANCHOR REQUIREMENTS TABLE

(1) NAILING FIN FASTENERS

| OPENING TYPE<br>(SUBSTRATE)                          | NAIL FIN TO OPENING FASTENER TYPE | MINIMUM<br>EMBED | MINIMUM<br>EDGE DIST. |
|--|-----------------------------------|------------------|-----------------------|
| MIN. 2X4 WOOD FRAME OR BUCK<br>(MIN. GR. 3 & G=0.55) | NO. 8 SMS SCREW                   | 1 1/4"           | 1/2"                  |
| MIN. 2X4 WOOD FRAME OR BUCK<br>(MIN. GR. 3 & G=0.55) | 11 GA. ROOFING NAIL               | 1 5/8"           | 1/2"                  |
| MIN. 1/8" THK A36 STEEL                              | NO. 8 GR. 5 SELF TAP/DRILL SCREW  | FULL             | 1/2"                  |
| MIN. 1/8" THK 6063-T5 ALUM.                          | NO. 8 GR. 5 SELF TAP/DRILL SCREW  | FULL             | 1/2"                  |

(1) WHEN SCREWS ARE USED WITH THE NAIL FIN, THEY MUST BE A WAFFLE HEAD SCREW OR HAVE A FLAT WASHER AT THE SCREW HEAD.

FOR MAX. FRAME WIDTH,  
SEE SINGLE WINDOW  
SIZE/PRESSURE  
TABLE ON THIS SHEET



EXTERIOR ELEVATION:  
SINGLE WINDOW

SCALE: 3/4" = 1'-0"


ALLOWABLE SINGLE WINDOW  
SIZE/PRESSURE TABLE


| MAXIMUM<br>FRAME HEIGHT<br>DIMENSION<br>(IN.) | MAXIMUM<br>FRAME WIDTH<br>DIMENSION<br>(IN.) | ALLOWABLE<br>PRESSURE<br>(+/- PSF) |
|---|--|------------------------------------|
| 64  | 45   | (1) 35                             |
| 83 1/2  | 47 1/2                                       | (2) 40                             |
| 60 1/2  | 35 1/2                                       | (1) 50                             |
| 71 1/2  | 35 1/2                                       | (2) 50                             |

- (1) WINDOW SHALL HAVE REINFORCEMENT AT CHECK RAILS ONLY.  
(2) WINDOW SHALL HAVE REINFORCEMENT AT CHECK RAILS AND STILES.

THESE DRAWINGS ARE APPLICABLE ONLY TO THE PRODUCT SPECIFIED. THEY MAY NOT BE USED FOR THE ASSEMBLY AND/OR INSTALLATION OF ANY OTHER PRODUCT NOR MAY THEY BE USED FOR RATIONAL AND/OR LOCAL APPROVAL OF ANY PRODUCT NOT PRODUCED BY THE MANUFACTURER STATED ON THESE DRAWINGS.


|   |                        |  |          |
|---|------------------------|--|----------|
| DRAWN BY:<br>W.R.M.   |                        | CHECKED BY:<br>W.W.S.  |          |
| PLOT:<br>1=16   |                        | DATE:<br>08/02/11  |          |
| NO.   | REVISION DESCRIPTION   | BY   | DATE     |
| A1  | UPDATE PER NEW TESTING | W.R.M.   | 07/23/13 |
| DRAWING TITLE<br>NEXT DIMENSION CLASSIC NON-IMPACT SINGLE HUNG WINDOW         |                        |  |          |
| CONSULTANTS<br>W. SCHAEFER ENGINEERING<br>& CONSULTING, P.A. (CA 6809)        |                        | MANUFACTURER<br>WINDSOR WINDOWS & DOORS<br>900 S. 19TH STREET<br>WEST DES MOINES, IA 50265<br>800-218-6186 |          |
| 7480 150TH COURT NORTH<br>PALM BEACH GARDENS, FL 33418<br>PHONE: 561-744-3424 |                        |  |          |
| CERTIFICATION<br>JUL 23 2013<br>WARREN W. SCHAEFER, P.E.<br>P.E. NO. 44135    |                        |  |          |
| DRAWING NO.<br>1769   |                        | REV.<br>A  |          |
| SHEET NO.<br>1 OF 3   |                        |  |          |






**EXTERIOR ELEVATION:**  
**TWIN WINDOW**  
 SCALE: 3/4" = 1'-0"

| ALLOWABLE TWIN WINDOW SIZE/PRESSURE TABLE                      |                                     |                              |
|--|-------------------------------------|------------------------------|
| MAXIMUM FRAME HEIGHT DIMENSION (IN.)                           | MAXIMUM FRAME WIDTH DIMENSION (IN.) | ALLOWABLE PRESSURE (+/- PSF) |
| 83 1/2   | 95 1/2                              | (2) 35                       |
| 60 1/2   | 71 1/2                              | (1) 45                       |
| (1) WINDOW SHALL HAVE REINFORCEMENT AT CHECK RAILS ONLY.       |                                     |                              |
| (2) WINDOW SHALL HAVE REINFORCEMENT AT CHECK RAILS AND STILES. |                                     |                              |




**EXTERIOR ELEVATION:**  
**TRIPLE WINDOW**  
 SCALE: 3/4" = 1'-0"


| ALLOWABLE DESIGN PRESSURE (TRIPLE WINDOWS)                 |
|--|
| +/-35 PSF  |
| WINDOW SHALL HAVE REINFORCEMENT AT CHECK RAILS AND STILES. |




|   |                      |   |      |
|---|----------------------|---|------|
| DRAWN BY:<br>W.R.M.   |                      | CHECKED BY:<br>W.W.S.   |      |
| PLOT:<br>1=16   |                      | DATE:<br>08/02/11   |      |
| NO.   | REVISION DESCRIPTION | BY  | DATE |
|   |                      |   |      |
| DRAWING TITLE<br><b>NEXT DIMENSION CLASSIC NON-IMPACT SINGLE HUNG WINDOW</b>      |                      |   |      |
| CONSULTANTS<br><b>W. W. SCHAEFER ENGINEERING &amp; CONSULTING, P.A. (CA 6809)</b> |                      | MANUFACTURER<br><b>WINDSOR WINDOWS &amp; DOORS</b>              |      |
| 7480 150TH COURT NORTH<br>PALM BEACH GARDENS, FL 33418<br>PHONE: 561-744-3424     |                      | 900 S. 19TH STREET<br>WEST DES MOINES, IA 50265<br>800-218-6186 |      |
| CERTIFICATION<br>JUL 28 2013<br>WARREN W. SCHAEFER, P.E.<br>P.E. NO. 44135        |                      | DRAWING NO.<br><b>1769</b>                                      |      |
| SHEET NO.<br><b>2</b> OF <b>3</b>   |                      | REV.<br><b>A</b>  |      |




SECTION A  
SCALE: 1/2 FULL




SECTION B  
SCALE: 1/2 FULL




SECTION C  
SCALE: 1/2 FULL



SECTION D  
SCALE: 1/2 FULL



|   |                      |  |      |
|---|----------------------|--|------|
| DRAWN BY:<br>W.W.S.   |                      | CHECKED BY:<br>W.W.S.  |      |
| PLOT:<br>1=2  |                      | DATE:<br>08/02/11  |      |
| NO.   | REVISION DESCRIPTION | BY   | DATE |
|   |                      |  |      |
|   |                      |  |      |
|   |                      |  |      |
|   |                      |  |      |
|   |                      |  |      |
| DRAWING TITLE<br>NEXT DIMENSION CLASSIC NON-IMPACT SINGLE HUNG WINDOW   |                      |  |      |
| CONSULTANTS<br>W. W. SCHAEFER ENGINEERING<br>& CONSULTING, P.A. (CA 6809)<br>7480 150TH COURT NORTH<br>PALM BEACH GARDENS, FL 33418<br>PHONE: 561-744-3424          |                      | MANUFACTURER<br>WINDSOR WINDOWS & DOORS<br>900 S. 19TH STREET<br>WEST DES MOINES, IA 50265<br>800-218-6186 |      |
| CERTIFICATION<br><br>JUL 28 2013<br>WARREN W. SCHAEFER, P.E.<br>P.E. NO. 44135 |                      |  |      |
| DRAWING NO.<br>1769   |                      | REV.<br>A  |      |
| SHEET NO.<br>3 OF 3   |                      |  |      |