



NOTES:

1. INSTALLATIONS SHOWN ON THIS DRAWING IS AS - TESTED INSTALLATION.
2. INSTALLATION ANCHORS SHALL BE OF TO ACHIEVE MINIMUM EMBEDMENT OF 1-1/2" INTO WOOD FRAMING MEMBER. EDGE DISTANCES SHALL BE SUFFICIENT TO PREVENT SPLITTING. 2" ROOFING NAILS SHALL HAVE A CORROSION RESISTANT FINISH.
3. WOOD FRAMING SHALL BE SPRUCE-PINE-FIR.
4. MAXIMUM SHIM SPACE SHALL BE 1/4" SPACES.
5. INSTALLATION ANCHORS SHALL BE LOCATED 4" FROM CORNERS AND 8" MAXIMUM ON CENTER SPACING.
6. THESE INSTRUCTIONS ADDRESS STRUCTURAL REQUIREMENTS ONLY. WINDOWS SHALL BE INSTALLED PER ASTM E2112 OR FMA/AAMA 100.
7. SMALLER WINDOWS OF THE SAME CONSTRUCTION AND EQUAL OR LESSER DESIGN PRESSURES ARE COVERED BY THIS DRAWING.

WINDSOR DOES NOT GUARANTEE ALIGNMENT OF DESIGN FEATURES OUTSIDE OF THOSE SPECIFIED ON THIS DRAWING. SEE ARCHITECTURAL REFERENCE MANUAL LOCATED AT WWW.WINDSORWINDOWS.COM. IT IS THE RESPONSIBILITY OF THE END USER TO UNDERSTAND THE SECTION DETAILS AND PRODUCT FEATURES ASSOCIATED WITH VARIOUS PRODUCT TYPES.

| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |



| | | | |
|--|------------|---|---------|
| CUSTOMER: | |  WINDSOR WINDOWS & DOORS A Woodgrain Millwork Company | |
| JOB: | | | |
| GRILLE OPTION: | | ORDER # | LINE #: |
| DESCRIPTION: ND SIGNATURE CASEMENT 3672 | | DATE: 5/26/15 | |
| PO # | APPRV# | DWG #: VCS-001-2 | |
| DRAWN BY: DJN | SCALE: NTS | | |