

GENERAL NOTES:

- ALL FASTENERS SHALL BE IN ACCORDANCE WITH THESE DRAWINGS. SPECIFIED ANCHOR EMBED TO BASE MATERIAL SHALL BE BEYOND WALL FINISH OR STUCCO.
- OPENINGS, BUCKING & BUCKING FASTENERS MUST BE PROPERLY DESIGNED & INSTALLED TO TRANSFER WIND LOADS TO THE STRUCTURE.
- THESE NON-IMPACT RATED WINDOW SYSTEM INSTALLATIONS ARE IN ACCORDANCE WITH AND MEET THE REQUIREMENTS OF THE FLORIDA BUILDING CODE (FBC).
- ALL ANCHORS SECURING WINDOW FRAME TO PRESSURE TREATED BUCKS OR WOOD FRAMING SHALL BE CAPABLE OF RESISTING CORROSION CAUSED BY THE PRESSURE TREATING CHEMICALS IN THE WOOD.
- MATERIALS, INCLUDING BUT NOT LIMITED TO STEEL SCREWS, THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF FLORIDA BUILDING CODE CHAPTER 20.
- TO THE BEST OF OUR KNOWLEDGE, THE WINDOWS SHOWN HEREIN ARE CERTIFIED & QUALITY ASSURED BY A FLORIDA STATE APPROVED CERTIFICATION/QA ENTITY & SHALL BE LABELED IN ACCORDANCE WITH THE FBC AND THE 9N-3 FLORIDA BUILDING COMMISSION SPECIFICATIONS. WINDOW ASSEMBLY IS NOT PART OF THIS DRAWING AND SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S QUALITY ASSURANCE SPECIFICATIONS & TESTING REPORTS.
- CERTIFICATION OF THESE WINDOW INSTALLATIONS SHALL BE CONSIDERED VOID IF ANY OF THE FOLLOWING APPLY: 1) THEY ARE INSTALLED WITHOUT A BUILDING PERMIT FROM THE APPLICABLE LOCAL BUILDING DEPARTMENT. 2) IF THEY ARE INSTALLED BY ANYONE OTHER THAN A LICENSED CONTRACTOR EXPERIENCED WITH WINDOW INSTALLATIONS. 3) IF CHANGES HAVE OCCURRED TO THE PRODUCT'S CERTIFICATION ENTITY'S CERTIFICATE THAT CAUSE THESE INSTALLATIONS TO BE INCORRECT OR INCONSISTENT WITH WHAT HAS BEEN TESTED.
- THE LEAST DESIGN PRESSURE SPECIFIED EITHER IN THIS DRAWING OR IN THE PRODUCTS CERTIFICATION SHALL CONTROL FOR THE INSTALLED WINDOW.
- THESE DRAWINGS CERTIFY THE WINDOW INSTALLATION ONLY. WATER PROOFING OF THE INSTALLED WINDOWS IS NOT PART OF THIS INSTALLATION CERTIFICATION. THAT RESPONSIBILITY SHALL BE THAT OF THE MANUFACTURER &/OR INSTALLER.

ALTERNATE ANCHOR/SUBSTRATE EVALUATION NOTE:


ALL ALTERNATE ANCHORS IN THEIR SPECIFIED SUBSTRATES HAVE BEEN ANALYZED IN ACCORDANCE WITH THEIR APPLICABLE STANDARD(S) AND ARE FOUND TO BE EQUIVALENT TO OR STRONGER THAN THE ANCHOR(S) USED IN TESTING WITH THIS PRODUCT.

INSTALLATION EVALUATION IS BASED ON APPLICABLE ANCHOR STANDARDS AND/OR INFORMATION & RESULTS FROM APPLICABLE TEST REPORTS. THE FLORIDA BUILDING CODE VERSION CONSIDERED WITH THE EVALUATION WAS THAT IN FORCE AT THE TIME OF THE EVALUATION. IN THE EVENT OF CODE VERSION CHANGES/UPDATES OR IN THE EVENT THAT NEW OR ADDITIONAL TESTING IS COMPLETED ON THE REFERENCED PRODUCT, PRIOR TO STATING CODE COMPLIANCE WITH THE STATE, THE MANUFACTURER SHALL CONFIRM WITH THE INSTALLATION EVALUATION ENGINEER OF RECORD THAT THE INSTALLATIONS SPECIFIED HERE-IN ARE CURRENT WITH THE THEN CURRENT TESTING, CODE AND APPLICABLE STANDARDS.

FRAME ANCHOR REQUIREMENTS TABLE

OPENING TYPE (SUBSTRATE)	FRAME/CLIP/BRICK MOLD TO OPENING FASTENER TYPE	MINIMUM EMBED	MINIMUM EDGE DIST.
FRAME SCREWS			
MIN. 2X4 WOOD FRAME OR BUCK (MIN. GR. 3 & G=0.55)	NO. 10 SMS OR WOOD SCREW	1 1/4"	3/4"
MIN. 18 GA. 33 KSI METAL STUD	NO. 10 GR. 5 SELF TAP/DRILL SCREW	FULL	1/2"
MIN. 1/8" THK A36 STEEL	NO. 10 GR. 5 SELF TAP/DRILL SCREW	FULL	1/2"
MIN. 1/8" THK 6063-T5 ALUM.	NO. 10 GR. 5 SELF TAP/DRILL SCREW	FULL	1/2"
C-90 CMU/2500 PSI CONCRETE	(1) 1/4" CONCRETE SCREW	1 1/4"	2"
INSTALLATION CLIP SCREWS (STANDARD TWO BEND CONDITION)			
MIN. 2X4 WOOD FRAME OR BUCK (MIN. GR. 3 & G=0.55)	NO. 8 SMS OR WOOD SCREW	1 3/8"	3/4"
MIN. 1/8" THK A36 STEEL	NO. 8 GR. 5 SELF TAP/DRILL SCREW	FULL	1/2"
MIN. 1/8" THK 6063-T5 ALUM.	NO. 8 GR. 5 SELF TAP/DRILL SCREW	FULL	1/2"
INSTALLATION CLIP SCREWS (ALTERNATE ONE BEND CONDITION)			
MIN. 2X6 WOOD FRAME OR BUCK (MIN. GR. 3 & G=0.55)	NO. 8 SMS OR WOOD SCREW	1 3/8"	3/4"
MIN. 1/8" THK A36 STEEL	NO. 8 GR. 5 SELF TAP/DRILL SCREW	FULL	1/2"
MIN. 1/8" THK 6063-T5 ALUM.	NO. 8 GR. 5 SELF TAP/DRILL SCREW	FULL	1/2"
BRICK MOLD FASTENERS			
MIN. 2X4 WOOD FRAME OR BUCK (MIN. GR. 3 & G=0.55)	NO. 6 SMS OR WOOD SCREW	1 3/8"	1/2"
MIN. 2X4 WOOD FRAME OR BUCK (MIN. GR. 3 & G=0.55)	10D GALV. FINISH NAILS	1 3/8"	1/2"

(1) CONCRETE SCREWS SHALL BE ELCO ULTRACONS (C.S.), ELCO CRETE-FLEX (S.S.), ITW RAMSET/RED HEAD TAPCONS (C.S. OR S.S.) OR HILTI KWIK-CON II (C.S OR S.S.).




EXTERIOR ELEVATION:
SINGLE WINDOW
(BRICK MOLD &
SCREW/CLIP INSTALLED)

SCALE: 3/4" = 1'-0"

BRICK MOLD INSTALLED ALLOWABLE
SINGLE WINDOW SIZE/PRESSURE TABLE

MAXIMUM FRAME DIMENSIONS		PERFORMANCE KIT REQUIRED	ALLOWABLE PRESSURE (PSF)
FRAME WIDTH (IN.)	FRAME HEIGHT (IN.)		
37 3/8	76 3/4	COASTAL	+/-50
35	89	COASTAL	+/-50
33	93	HIGH	+/-50
45 3/8	76 3/4	HIGH	+/-50



EXTERIOR ELEVATION:
SINGLE WINDOW
(SCREW OR CLIP ONLY INSTALLED)

SCALE: 3/4" = 1'-0"

SCREW OR CLIP INSTALLED ALLOWABLE
SINGLE WINDOW SIZE/PRESSURE TABLE

MAXIMUM FRAME DIMENSIONS		PERFORMANCE KIT REQUIRED	ALLOWABLE PRESSURE (PSF)
FRAME WIDTH (IN.)	FRAME HEIGHT (IN.)		
37 3/8	76 3/4	COASTAL	+/-50
35	89	COASTAL	+/-50
33	93	HIGH	+/-50

THESE DRAWINGS ARE APPLICABLE ONLY TO THE PRODUCT SPECIFIED. THEY MAY NOT BE USED FOR THE ASSEMBLY AND/OR INSTALLATION OF ANY OTHER PRODUCT NOR MAY THEY BE USED FOR RATIONAL AND/OR LOCAL APPROVAL OF ANY PRODUCT NOT PRODUCED BY THE MANUFACTURER STATED ON THESE DRAWINGS.

DRAWN BY:
W.R.M.

CHECKED BY:
W.W.S.

PLOT:
1=16

DATE:
10/09/07

NO.	REVISION DESCRIPTION	DATE	BY	W.R.M.	W.R.M.
A1	UPDATE TO PRESENT STANDARDS	06/17/08			
B1	UPDATE TO PRESENT STANDARDS & NEW TESTING	03/07/12			

LEGEND HBR NON-IMPACT DOUBLE HUNG WINDOW

MANUFACTURER
WINDSOR WINDOWS & DOORS
900 S. 19TH STREET
WEST DES MOINES, IA 50265
800-218-6186




CONSULTANTS
W. W. SCHAEFER ENGINEERING
& CONSULTING, P.A. (CA 6809)
7480 150TH COURT NORTH
PALM BEACH GARDENS, FL 33418
PHONE: 561-744-3424

CERTIFICATION
WARREN W. SCHAEFER, P.E.
P.E. NO. 44135

DRAWING NO.
1558

REV.
B

SHEET NO.
1 OF 3






DRAWN BY: W.R.M.		CHECKED BY: W.W.S.																													
PLOT: 1=2		DATE: 10/09/07																													
<table><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr></table>																															
<table><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td></tr></table>																															
<table><tr><td colspan="2">DRAWING TITLE LEGEND HBR NON-IMPACT DOUBLE HUNG WINDOW</td><td colspan="2"><table><tr><td colspan="2">CONSULTANTS W. W. SCHAEFER ENGINEERING & CONSULTING, P.A.</td><td colspan="2">MANUFACTURER WINDSOR WINDOWS & DOORS</td></tr><tr><td colspan="2">7480 150TH COURT NORTH PALM BEACH GARDENS, FL 33418 PHONE: 561-744-3424</td><td colspan="2">102 MAIN STREET WEST DES MOINES, IA 50265 800-218-6186</td></tr></table></td></tr></table>				DRAWING TITLE LEGEND HBR NON-IMPACT DOUBLE HUNG WINDOW		<table><tr><td colspan="2">CONSULTANTS W. W. SCHAEFER ENGINEERING & CONSULTING, P.A.</td><td colspan="2">MANUFACTURER WINDSOR WINDOWS & DOORS</td></tr><tr><td colspan="2">7480 150TH COURT NORTH PALM BEACH GARDENS, FL 33418 PHONE: 561-744-3424</td><td colspan="2">102 MAIN STREET WEST DES MOINES, IA 50265 800-218-6186</td></tr></table>		CONSULTANTS W. W. SCHAEFER ENGINEERING & CONSULTING, P.A.		MANUFACTURER WINDSOR WINDOWS & DOORS		7480 150TH COURT NORTH PALM BEACH GARDENS, FL 33418 PHONE: 561-744-3424		102 MAIN STREET WEST DES MOINES, IA 50265 800-218-6186																	
DRAWING TITLE LEGEND HBR NON-IMPACT DOUBLE HUNG WINDOW		<table><tr><td colspan="2">CONSULTANTS W. W. SCHAEFER ENGINEERING & CONSULTING, P.A.</td><td colspan="2">MANUFACTURER WINDSOR WINDOWS & DOORS</td></tr><tr><td colspan="2">7480 150TH COURT NORTH PALM BEACH GARDENS, FL 33418 PHONE: 561-744-3424</td><td colspan="2">102 MAIN STREET WEST DES MOINES, IA 50265 800-218-6186</td></tr></table>		CONSULTANTS W. W. SCHAEFER ENGINEERING & CONSULTING, P.A.		MANUFACTURER WINDSOR WINDOWS & DOORS		7480 150TH COURT NORTH PALM BEACH GARDENS, FL 33418 PHONE: 561-744-3424		102 MAIN STREET WEST DES MOINES, IA 50265 800-218-6186																					
CONSULTANTS W. W. SCHAEFER ENGINEERING & CONSULTING, P.A.		MANUFACTURER WINDSOR WINDOWS & DOORS																													
7480 150TH COURT NORTH PALM BEACH GARDENS, FL 33418 PHONE: 561-744-3424		102 MAIN STREET WEST DES MOINES, IA 50265 800-218-6186																													
<table><tr><td colspan="2">CERTIFICATION </td><td colspan="2">MAR 09 2012 WARREN W. SCHAEFER, P.E. P.E. NO. 44135</td></tr></table>				CERTIFICATION 		MAR 09 2012 WARREN W. SCHAEFER, P.E. P.E. NO. 44135																									
CERTIFICATION 		MAR 09 2012 WARREN W. SCHAEFER, P.E. P.E. NO. 44135																													
DRAWING NO. 1558		REV. B																													
SHEET NO. 2 OF 3																															

Diagram illustrating the cross-section of a window frame assembly, showing the relationship between the frame, sash, and surrounding structure. Key components and labels include:

- SPACE IS WITHIN DIMENSIONAL REQUIREMENTS SHOWN (SECTION).
- SEALANT BY OTHERS
- FRAME ANCHOR REQUIREMENTS TABLE
- FRAME SCREW ELEVATION & "FRAME ANCHOR REQUIREMENTS TABLE"
- EXTERIOR

(HEAD SECTION SHOWN; SILL & SIDES ARE INSTALLED THE SAME)
(FOR DETAIL NOT SHOWN, SEE OTHER SECTIONS)

1
INSTALLATION
CLIP

SEALANT BY—
OTHERS

NO. 8 X 5/8"-
SCREWS
(2 PER CLIP)

EXTERIOR

(HEAD SECTION SHOWN; SILL & SIDES ARE INSTALLED THE SAME)
(FOR DETAIL NOT SHOWN, SEE OTHER SECTIONS)


1
INSTALLATION
CLIP

SEALANT BY—
OTHERS


NO. 8 X 5/8"
SCREWS
(2 PER CLIP)


EXTERIOR

(HEAD SECTION SHOWN; SILL & SIDES ARE INSTALLED THE SAME)
(FOR DETAIL NOT SHOWN, SEE OTHER SECTIONS)



① FRAME INSTALLATION CLIP
(33 KSI STEEL)



DRAWING NO. 1558	SHEET NO. 3 OF 3	CERTIFICATION  MAR 09 2012 WARREN W. SCHAEFFER, P.E. P.E.	DRAWING TITLE LEGEND HBR NON-IMPACT DOUBLE HUNG WINDOW	CONSULTANTS W. W. SCHAEFFER ENGINEERING & CONSULTING, P.A. 7480 150TH COURT NORTH PALM BEACH GARDENS, FL 33418 PHONE: 561-744-3424		MANUFACTURER WINDSOR WINDOWS & DOORS 102 MAIN STREET WEST DES MOINES, IA 50265 800-218-6186	
				NO. REVISION DESCRIPTION BY DATE	DRAWN BY: W.R.M. CHECKED BY: W.W.S. PLOT: 1=2 DATE: 10/09/07		