Pinnacle Series

PRIMED AWNING

ELEVATIONS : OPERATING / STATIONARY

SCALE: 1/8" = 1'-0"

			Mas. Opg. Primed	2-3 9/16	2-7 9/16	2-9 9/16	2-11 9/16	3-3 9/16	3-9 9/16	4-3 9/16
			Mas. Opg. Clad	2-0 3/4	2-4 3/4	2-6 3/4	2-8 3/4	3-0 3/4	3-6 3/4	4-0 3/4
			Rough Opg. Primed	2-0 3/4	2-4 3/4	2-6 3/4	2-8 3/4	3-0 3/4	3-6 3/4	4-0 3/4
			Rough Opg. Clad	2-0 3/4	2-4 3/4	2-6 3/4	2-8 3/4	3-0 3/4	3-6 3/4	4-0 3/4
			Frame	2-0	2-4	2-6	2-8	3-0	3-6	4-0
			Glass	20	24	26	28	32	38	44
1-8 15/16	1-6 1/2	1-7 1/4	1-6 1/2	1-6	14	2014	2414	2614	2814	3214	3814	4414
1-10 15/16	1-8 1/2	1-9 1/4	1-8 1/2	1-8	16	2016	2416	2616	2816	3216	3816	4416
2-2 15/16	2-0 1/2	2-1 1/4	2-0 1/2	2-0	20	2020	2420	2620	2820	3220	3820	4420
2-6 15/16	2-4 1/2	2-5 1/4	2-4 1/2	2-4	24	2024	2424	2624	2824	3224	3824	4424
2-8 15/16	2-6 1/2	2-7 1/4	2-6 1/2	2-6	26	2026	2426	2626	2826	3226	3826	4426
3-2 15/16	3-0 1/2	3-1 1/4	3-0 1/2	3-0	32					3232	3832	4432

OPERATION



OPERATING STATIONARY

OTHER GRILLE PATTERN



PRAIRIE

UNIT SIZE INFORMATION

FOR CLAD BRICKMOULD
- ADD 2 13/16" TO FRAME WIDTH
- ADD 1 3/4" TO FRAME HEIGHT*

FOR CLAD WILLIAMSBURG
- ADD 6 1/2" TO FRAME WIDTH
- ADD 3 5/8" TO FRAME HEIGHT*

FOR PRIMED WM-180
- ADD 2 13/16" TO FRAME WIDTH
- ADD 2 13/32" TO FRAME HEIGHT*

FOR PRIMED 3 1/2" FLAT CASING
- ADD 5 13/16" TO FRAME WIDTH
- ADD 3 15/16" TO FRAME HEIGHT*

FOR PRIMED 4 1/2" BACKBAND
- ADD 7 13/16" TO FRAME WIDTH
- ADD 4 15/16" TO FRAME HEIGHT*

FOR PRIMED 5 1/2" FLAT CASING
- ADD 9 13/16" TO FRAME WIDTH
- ADD 5 15/16" TO FRAME HEIGHT*

FOR PRIMED WILLIAMSBURG
- ADD 5 3/8" TO FRAME WIDTH
- ADD 3 11/16" TO FRAME HEIGHT*

FOR PRIMED PLANTATION
- ADD 5 13/16" TO FRAME WIDTH
- ADD 5 15/16" TO FRAME HEIGHT*

* ADD ADDITIONAL 1" FOR BULLNOSE SILL

NOTES:
CLAD MASONRY OPENINGS ARE FOR STANDARD FRAME WITH NO CASING
PRIMED MASONRY OPENINGS ARE FOR STANDARD 180 BRICKMOULD

NOTE:
ADD 3/4" TO UNIT WIDTH & 1/2" TO UNIT HEIGHT
TO CALCULATE MASONRY OPENING

6/8/16